BRUHATH BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

Name of Work : Improvements to drain at 6th & 7th Main of Ramaiah Layout (Around Park opp Pavagada Co.Op Bnak) in Bagalagunte in Ward No: 14

Sl. No	Description	Unit	Qty	Rates	
				In Figs	In Words
1	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 metres and an average lift upto 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	301.20	203.78	Rupees two hundred three and seventy-eight paise only
2	Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs, with 40 mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth,including cost of all materials, labour HOM of machinery curing complete as per specifications.	Cum	45.18	5159.02	Rupees five thousand, one hundred fifty-nine and zero two paise only
3	Design mix M 20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @ 0.46 cum, with superplastisiser @ 3lts confirming to IS9103-1999 Reaffirmed-2008 i) upto 5m height	Cum	101.66	6965.26	Rupees six thousand, nine hundred sixty-five and twenty-six paise only
4	Supplying, fitting and placing TMT bar reinforcement in sub-structure as per drawing and Technical Specifications complete as per specifications. MORTH Specification No.1600 & 2200 TMT Bars FE 500	Tonne	7.86	66482.14	Rupees sixty-six thousand, four hundred eighty-two and fourteen paise only
5	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per spec	Sqm	903.60	310.58	Rupees three hundred ten and fifty-eight paise only
6	Providing and laying precast drain cover slab of 100mm thickness in CM 1:3 including cost of all materials labour curing transportio, loading, unloading etc., as per direction of the engineer in charges	Sqm	225.90	1957.00	Rupees one thousand, nine hundred fifty-seven only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division